

# Forklift Telehandler (High Risk) Work Instruction

Document ID: SCEE-BS-HS-WIN-0027

# Authority

	Title	Name	Date
Owner	HSEQ Manager	Anthony Gollan	26/07/2023
Reviewer	HSEQ Manager	Anthony Gollan	26/07/2023
Approver	Group Manager Business Services	Jamie Yeing	26/07/2023

# History

Revision	Date	Amended By (Name)	Details of Amendment
0.0	06/01/2015	Codie Davies	Document renumbered, supersedes WI-OHS- 006
0.1	21/06/2016	Anthony Gollan	Document reviewed to incorporate 5 Star Commitment requirements.
0.2	22/08/2016	Patrick Gabato	Updated format
1.0	30/08/2016	Patrick Gabato	Issued for use
2.0	12/07/2018	Anthony Gollan	Document reviewed with Loading and Unloading added to document.
3.0	21/10/2020	Anthony Gollan	Document reviewed
4.0	26/07/2023	Vanessa Placheta	SCEE Electrical Branding and Review



#### Work Instruction

# **Table of Contents**

1	Purpose3		3
2	Definitions		3
3	Responsibilities		
4	Flow Chart		
5	Activities		
	5.1	Operator Competency	4
	5.2	Duty of Care	4
	5.3	Plant Logbook	4
	5.4	Seat belts	4
	5.5	Work Load	4
	5.6	Considerations	5
	5.7	Loading and Unloading	5
	5.8	Emergency Response Plan	5
6	References		6
7	Related Documents		6



#### 1 Purpose

To provide Southern Cross Electrical Engineering Limited (SCEE) employees with the necessary guidance and information to ensure that while working on forklift or telehandler activities they will be done in a safe and efficient manner. This Work Instruction (WI) will apply to all SCEE work sites and locations where forklift/ telehandler activities are carried out.

#### 2 Definitions

Term	Definition
JHA	Job Hazard Analysis
LF	Fork-lift truck
WI	Work Instruction

#### **3** Responsibilities

-		
Role	Responsibility	
Project Manager	• Ensure full compliance with the requirements of this work instruction.	
Site Manager	<ul> <li>Audit and Monitor Compliance with this work instruction.</li> </ul>	
HSE Advisor	<ul> <li>Audit and Monitor Compliance with this work instruction.</li> </ul>	
Supervisor	<ul> <li>Conduct workplace inspections and enforce compliance with this work instruction.</li> </ul>	
Employees	Comply with the requirements of this work instruction.	

#### 4 Flow Chart

#### N/A

# 5 Activities

All forklift and telehandler activity is to be carried out in accordance with AS 2359 and relevant codes of practices and guidelines.

#### Refer: AS 2359

Forklift and telehandler operations have been identified as a High Risk Work Activity by SCEE.

The below is to be read in conjunction with SCEE's 5 Star Commitment Procedure SCEE-HS-BS-PRO-0027. The intent of this procedure is to eliminate the risk of fatalities, injuries and events arising from lifting operations.

#### Refer: SCEE-HS-BS-PRO-0027 5 Star Commitment Procedure



# 5.1 Operator Competency

Forklift/ telehandler's are only to be operated by certified and competency assessed operators. Operators are to hold a current License to Perform High Risk Work endorsed for fork lift truck. Site procedures may also dictate that operators undergo a Verification of Competency test. A LF High Risk Work license is required to operate any forklift/telehandler within SCEE.

# 5.2 Duty of Care

This WI and associated Job Hazard Analysis (JHA) aims to ensure that all employees are aware of the need to provide safe interactions and clear communications with other workgroups involved or working near the task.

The statutory requirements regarding duty of care to both SCEE and its employees remain the first priority at all times.

## 5.3 Plant Logbook

SCEE management will ensure that forklift/ Telehandlers operated on site carry the current plant logbook and manufacturer's operation and maintenance manuals at all times. Details of maintenance history and modifications shall be entered into the plant logbook. Any fault/problem identified is to be recorded in the logbook, and reported to the supervisor so as repairs/maintenance can be scheduled.

## 5.4 Seat belts

All forklift/ Telehandlers will be fitted with a seatbelt, which must be worn by the operator at all times during operation.

## 5.5 Work Load

Where lifting attachments are fixed to the forklift/ telehandler the operator shall ensure that the equipment is not loaded beyond its design capacity. Attachments shall be securely fastened to the machine to prevent dislodgement.

Loads being transported are subject to different forces than those present with a stationary lift. In addition, condition of the surface over which the load is being moved can greatly influence stability. Telehandler arms should be retracted when loads are being moved. Loads are not to be slung from Telehandlers or forklifts unless Project Manager has approved.

Where the load is large and obscures vision, the machine must be travelled backwards or a spotter used. The spotter shall be responsible for clearing a safe passage (this includes checking for clearances under such structures as conveyors etc.) for the forklift/ telehandler and traffic management.



# 5.6 Considerations

The following shall be reviewed and considered in the JHA as applicable:

- Ground conditions;
- Personnel requirements and individual responsibilities;
- Environmental conditions (wind, rain, dust, storms, lightning etc.);
- Transportation requirements;
- Stabilization during transportation;
- Means of communication; and
- Exclusion zones and barrier/barricade requirements.
- Vicinity permits if work is to be conducted within proximity limits to high voltage overhead lines; and
- Weight and dimensions of object to be lifted/transported.

#### Refer: SCEE-BS-HS-TEM-0008 Job Hazard Analysis

## 5.7 Loading and Unloading

When loading or unloading on site, the following shall be adhered to:

- Inspect loads before un-securing to ensure it is safe and cannot not shift once binders are released.
- Personnel are not permitted to stand on the offside of the truck during loading and unloading. This area is to be demarcated with cones and flags and personnel are to monitor that this area is clear prior to any touching or movement of loads.
- No person/s is permitted to be on or climb onto an open tray without appropriate working at height protection; fall restraint protection such as gates or side rail protection will be a minimum of 900mm.
- Unloading or loading in non-designated areas will be performed away from traffic flow to minimise interface issues.
- Due to the inherent risks associated with lifting, moving or relocating transportable buildings, this task shall only be conducted using a crane. The use of a 'Tilt-Tray' vehicle is permitted only once a risk assessment has been undertaken.
- Designated loading and unloading areas should be utilised where possible.
- Spotter should be used as required.
- Drivers shall remain clear of loading and unloading activities and to remain under the direction of the SCEE escort.
- The off side during loading and unloading should be a no go zone for all personnel;

## 5.8 Emergency Response Plan

The Emergency Response Plan incorporated into the JHA should list the relevant contact details of Paramedics. The JHA should also indicate any team member who is first aid qualified.

Each Employee directed to complete a forklift or telehandler task has responsibilities to incorporate this WI into their scope of work.



Work Instruction

## 6 References

Documents, both internal and external, that are referenced within the content of this work instruction, including Australian and International Standards and legislation.

Document ID	Document Title
AS 2359	Powered Industrial Trucks
SCEE-HS-BS-PRO-0027	5 Star Commitment Procedure
SCEE-BS-HS-TEM-0008	Job Hazard Analysis

# 7 Related Documents

Related documents are those that have a relationship with this document, for example if this was the Operational Risk Management procedure related documents would include the work instruction to complete a JHA, the JHA template, Take 5 work instruction and booklet, etc.

Document ID	Document Title